



Cost Savings Case Study: Distribution Center

South Section: Roof Drains

Initial Design:

- Trenching: 20 lines of 388'2" for a total 7763'4" of internal trenching
- Pipe:

10 lines of 475'8" @ 8" Ø

10 lines of 437'2" @ 8" Ø

Total Pipe = 9128'2" @ 8" Ø

MIFAB Design:

- Elimination of all internal trenching saving 7763'4" of trenching
- Pipe runs completely flat in the ceiling
- Combined 2 drains into one run eliminating half of the pipe work:

10'11"@4"Ø

286'31/2"@5"Ø

805'10"@6"Ø

4069'3"@8"Ø

986'3" @ 10" Ø

Total Pipe = $6158'6\frac{1}{2}"$

North Section: Gutter Roof Drains

Initial Design:

41 Downspouts using 6"Ø
Average height of 58'
Total Pipe = 2378'

MIFAB Design:

- Total count is 21 RWP's using mainly 4" Ø

56'@3"Ø

1099'101/2"@4"Ø

30'@6"Ø

Total Pipe = $1185'10\frac{1}{2}"$

Additional Cost Savings

- Savings of Labor

Half the amount of pipe to install

Smaller diameter pipe easier to hang

Less gutter drains to install

- Reduced Calendar Days

No Internal Trenching

- Smaller diameter pipe also means:

Smaller Fittings

Smaller Couplings

Smaller Hangers

Smaller Insulation

Ability to consolidate civil connections





What's your cost? What's your savings?

Please enter in your own values to see what the cost savings on this distribution center project would have been for your company