

Location: \_\_\_\_\_




**R1150-SPEC**


**COMBINED ROOF DRAIN AND SECONDARY OVERFLOW  
SYSTEM WITH LOOSE SET SUMP RECEIVER**

**Specification:** MIFAB® Series R1150-SPEC combined roof drain and secondary overflow system, consisting of a galvanized sump receiver; two lacquered cast iron roof drain bodies with anchor flanges, cast iron waterproofing membrane clamp rings with integral gravel stops, one 4" (102) diameter adjustable ABS overflow standpipe and two self-locking cast iron dome strainers with a free area of 43 square inches each.

**Function:** Used in any type of conventional or flat roofs where a safety overflow, which receives water only when the accumulation is greater than the height of the standpipe is required to be located beside a standard roof drain. The standpipe can be adjusted to attain the desired overflow water depth. Dome provides for efficient drainage of rainwater and prevents debris from entering the drain line. Anchor flange and membrane clamp with tongue in groove design provides for secure grip of membrane and roof flashing materials.



**PARTS:**



MODEL NO.	PIPE SIZE	BODY HEIGHT				
		NO HUB (STANDARD)	PUSH ON (P)	THREADED (T)	INSIDE CAULK (X)	PVC (-30) / ABS (-31)
R1152-SPEC	2" (51)	3" (76)	3 3/8" (86)	2 1/4" (57)	3 3/4" (95)	2 5/8" (67)
R1153-SPEC	3" (76)	3" (76)	3 3/8" (86)	2 5/8" (67)	3 3/4" (95)	3 1/4" (83)
R1154-SPEC	4" (102)	3" (76)	3 3/8" (86)	2 5/8" (67)	3 3/4" (95)	3 1/2" (89)
R1155-SPEC	5" (127)	3" (76)	-	2 5/8" (67)	6 7/8" (175)	-
R1156-SPEC	6" (152)	3' 1/2' (89)	6 7/8" (175)	-	-	-

Suffix	Description	(Standard)	No hub outlets
-6	Vandal proof domes	-BA	Minimum 51% material cost made in the USA
-11	Acid resistant epoxy coating	-E	Adjustable extension
-12	Galvanized metal domes	-EG	Galvanized Adjustable extension
-12A	Galvanized bodies and membrane clamps	-G	Stainless steel ballast guards
-13	Galvanized bodies, membrane clamps and domes	P	Push on outlets
-28	Stainless steel bodies (Type 304) (2", 3", 4")	-PA	Pennsylvania Steel Act compliant product
-30	PVC socket connection bodies	T	Threaded outlets (2", 3", 4")
-31	ABS socket connection bodies	-U	Underdeck clamps
-81	Rough bronze domes	-U3	Underdeck clamps with cutaway side
-83	Stainless steel mesh screen over domes	-W-1	Water proofing flange
-90	Threaded side outlets (2", 3", 4")	X	Inside caulk outlets (2", 3", 4")
-90NH	No Hub side outlets (cast iron only) (2", 3", 4")	-XJ	Vertical expansion joint (see R1900)

CALIFORNIA PROPOSITION 65 WARNING. This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm.

Job Name: \_\_\_\_\_ Page No: \_\_\_\_\_  
Section No: \_\_\_\_\_ Contractor: \_\_\_\_\_  
Schedule No: \_\_\_\_\_ Purchase Order No: \_\_\_\_\_